

# Neutron Wall Loading Update

L. El-Guebaly, A. Jaber, A. Robinson, D. Henderson Fusion Technology Institute University of Wisconsin-Madison http://fti.neep.wisc.edu/UWNeutronicsCenterOfExcellence


> **Contributor:** X. Wang (UCSD)

**ARIES Project Meeting** 

Bethesda, MD April 4 - 5, 2011




## ARIES-ACT New FW/Div Configuration






# New vs. Old FW/Div Configuration





# 3-D NWL Model

- Includes:
  - Plasma boundary
  - IB & OB FW
  - IB & OB div plates and dome.
- FW and divertor <u>segmented</u> vertically and radially to improve accuracy.
- 10 million particle history.
- Statistical error < 1%.




#### MCNP 3-D Model



# Neutron Source Sampling

**Options**:

- **1.** Uniform within plasma boundary.
  - <u>Unrealistic</u>, but used to check geometry (1/2011 ARIES presentation by El-Guebaly).
- 2. Three-nested source regions with variable intensity peaking at magnetic axis:
  - <u>Good approximation.</u>
  - Intensities borrowed from ARIES-RS: 63%, 32%, 5%.
- 3. Actual distribution:
  - Source density distributed on R-Z grid <u>not available yet</u>.
  - Results identical to 3-nested source, except for 10% higher peak at IB midplane (refer to 5/2008 NWL presentation by Wilson).




#### MCNP 2-D Plot (3-nested Source Regions)



#### Three-nested Source Regions Within Plasma


# Neutron Source Intensity: 63%, 32%, 5%



(Example: 10,000 particles random sampling)




## **IB** and **OB** Results



7



#### **Divertor Results**



Machine Ave NWL (P <sub>f</sub> x 0.8/an (a) 10 cm from plasma sur	· ·	2.8
Peak Div NWL Ave Div NWL	8	2 0.7

Peak Div

NWL



# Summary of NWL Results

Machine Ave NWL (P <sub>f</sub> x 0.8/area):	
@ 10 cm from plasma surface	2.8
Peak IB NWL	3.3
Ave IB NWL	2.3
Peak OB NWL	4.7
Ave OB NWL	3.6
Peak div NWL	2
Ave div NWL	0.7

#### Peak to average NWL = 1.68



- Peak NWLs will be used to redefine radial builds for ARIES-ACT:
  - 3.3 MW/m<sup>2</sup> for IB
  - 4.7 MW/m<sup>2</sup> for OB
  - 2 MW/m<sup>2</sup> for divertor.

• For ASC, peak to average NWL = 1.68 (not 1.5).